
CERTIFIED ASSOCIATE CONSTRUCTOR (CAC) LEVEL 1 PRACTICE EXAM (SAMPLE)

STUDY GUIDE



SAMPLE STUDY GUIDE WITH LIMITED QUESTIONS

VISIT US ONLINE FOR THE FULL VERSION STUDY GUIDE

https://caclevel1.examzify.com

Copyright © 2026 by Examzify - A Kaluba Technologies Inc. product.

ALL RIGHTS RESERVED.

No part of this book may be reproduced or transferred in any form or by any means, graphic, electronic, or mechanical, including photocopying, recording, web distribution, taping, or by any information storage retrieval system, without the written permission of the author.

Notice: Examzify makes every reasonable effort to obtain accurate, complete, and timely information about this product from reliable sources.

SAMPLE

Table of Contents

Copyright 1

Table of Contents 2

Introduction 3

How to Use This Guide 4

Questions 5

Answers 8

Explanations 10

Next Steps 16

SAMPLE

Introduction

Preparing for a certification exam can feel overwhelming, but with the right tools, it becomes an opportunity to build confidence, sharpen your skills, and move one step closer to your goals. At Examzify, we believe that effective exam preparation isn't just about memorization, it's about understanding the material, identifying knowledge gaps, and building the test-taking strategies that lead to success.

This guide was designed to help you do exactly that.

Whether you're preparing for a licensing exam, professional certification, or entry-level qualification, this book offers structured practice to reinforce key concepts. You'll find a wide range of multiple-choice questions, each followed by clear explanations to help you understand not just the right answer, but why it's correct.

The content in this guide is based on real-world exam objectives and aligned with the types of questions and topics commonly found on official tests. It's ideal for learners who want to:

- Practice answering questions under realistic conditions,
- Improve accuracy and speed,
- Review explanations to strengthen weak areas, and
- Approach the exam with greater confidence.

We recommend using this book not as a stand-alone study tool, but alongside other resources like flashcards, textbooks, or hands-on training. For best results, we recommend working through each question, reflecting on the explanation provided, and revisiting the topics that challenge you most.

Remember: successful test preparation isn't about getting every question right the first time, it's about learning from your mistakes and improving over time. Stay focused, trust the process, and know that every page you turn brings you closer to success.

Let's begin.

SAMPLE

How to Use This Guide

This guide is designed to help you study more effectively and approach your exam with confidence. Whether you're reviewing for the first time or doing a final refresh, here's how to get the most out of your Examzify study guide:

1. Start with a Diagnostic Review

Skim through the questions to get a sense of what you know and what you need to focus on. Your goal is to identify knowledge gaps early.

2. Study in Short, Focused Sessions

Break your study time into manageable blocks (e.g. 30 – 45 minutes). Review a handful of questions, reflect on the explanations.

3. Learn from the Explanations

After answering a question, always read the explanation, even if you got it right. It reinforces key points, corrects misunderstandings, and teaches subtle distinctions between similar answers.

4. Track Your Progress

Use bookmarks or notes (if reading digitally) to mark difficult questions. Revisit these regularly and track improvements over time.

5. Simulate the Real Exam

Once you're comfortable, try taking a full set of questions without pausing. Set a timer and simulate test-day conditions to build confidence and time management skills.

6. Repeat and Review

Don't just study once, repetition builds retention. Re-attempt questions after a few days and revisit explanations to reinforce learning. Pair this guide with other Examzify tools like flashcards, and digital practice tests to strengthen your preparation across formats.

There's no single right way to study, but consistent, thoughtful effort always wins. Use this guide flexibly, adapt the tips above to fit your pace and learning style. You've got this!

SAMPLE

Questions

SAMPLE

1. In a parallel circuit, how do you calculate the total resistance?

A. Add the individual resistances together.

B. Take the reciprocal of the sum of reciprocals of each resistance.

C. Multiply all resistances together.

D. Take the average of the resistances.

2. What type of analysis is used to identify potential project risks?

A. Financial analysis

B. Quality analysis

C. Risk assessment

D. Work breakdown analysis

3. Which of the following contract types is generally considered to have the most risk for the contractor?

A. lump sum

B. unit price

C. cost plus

D. cost plus with GMP

4. Which factor is most important in determining the critical path in project scheduling?

A. Early start times

B. Late start times

C. Activity durations

D. Resource availability

5. What is the primary role of the construction superintendent?

A. To handle all financial transactions

B. To oversee day-to-day construction operations on the job site

C. To design the architectural plans and layouts

D. To recruit and train subcontractors

SAMPLE

6. For what type of project would you most likely use a trenching machine?

A. Residential basement excavation

B. Installing utility lines

C. Road construction

D. Site grading

7. When should meeting minutes be distributed?

A. about one day prior to the meeting

B. at the beginning of the meeting

C. about one day after the meeting

D. any time during the project

8. In construction, what do the term "submittals" refer to?

A. Final project delivery documents

B. Documents for acquiring insurance

C. Documents provided for approval before starting work

D. Payments made to contractors

9. Which management system was developed based on Toyota's Production System?

A. TQM

B. Six Sigma

C. Lean

D. ISO 9000

10. What document defines the project's objectives and overall purpose?

A. Project Plan

B. Project Charter

C. Statement of Work

D. Risk Management Plan

SAMPLE

Answers

SAMPLE

1. B
2. C
3. A
4. C
5. B
6. B
7. C
8. C
9. C
10. B

SAMPLE

Explanations

SAMPLE

1. In a parallel circuit, how do you calculate the total resistance?

A. Add the individual resistances together.

B. Take the reciprocal of the sum of reciprocals of each resistance.

C. Multiply all resistances together.

D. Take the average of the resistances.

In a parallel circuit, the total resistance is calculated by taking the reciprocal of the sum of the reciprocals of each individual resistance. This method reflects how current divides among the multiple pathways provided by each branch in the circuit. When resistors are connected in parallel, they each provide an alternative path for current to flow. As a result, the overall resistance of the circuit decreases compared to any individual resistor. Mathematically, this relationship can be expressed as: 1 / R_total = 1 / R1 + 1 / R2 + 1 / R3 + ... where R1, R2, R3, etc., are the resistances of the individual branches. The reciprocal nature of this calculation highlights that adding pathways for current flow reduces the overall opposition in the circuit. In contrast, simply adding the individual resistances together applies to series circuits, where resistors are connected end-to-end and the current must pass through each one sequentially. Multiplying resistances applies to certain configurations but not for a parallel setup. Averaging the resistances would not yield a meaningful representation of how resistances interact in parallel circuits. Therefore, understanding the use of reciprocals in this context is crucial for correctly calculating total resistance in parallel arrangements.

2. What type of analysis is used to identify potential project risks?

A. Financial analysis

B. Quality analysis

C. Risk assessment

D. Work breakdown analysis

The use of risk assessment is essential for identifying potential project risks. This type of analysis involves systematically reviewing and evaluating risks that could impact a project's success. It helps project managers and teams pinpoint uncertainties that may arise during the project lifecycle, assessing their likelihood of occurrence and potential impact on project objectives. By conducting a risk assessment, teams can create a risk register, prioritize risks according to their severity, and develop appropriate risk response strategies to mitigate or manage these risks effectively. This proactive approach is crucial for ensuring that risks are identified early on, allowing the team to plan for uncertainties instead of reacting to problems when they arise. While financial analysis focuses on the budget and economic implications of a project, quality analysis looks at the standards and expectations for deliverable quality. Work breakdown analysis is concerned with dividing the project into smaller, manageable components. These methodologies do not specifically address the identification and evaluation of risks, which is the primary goal of risk assessment.

SAMPLE

3. Which of the following contract types is generally considered to have the most risk for the contractor?

A. lump sum

B. unit price

C. cost plus

D. cost plus with GMP

A lump sum contract is generally considered to carry the most risk for the contractor because the contractor agrees to complete the project for a fixed total price. This arrangement places the burden on the contractor to accurately estimate all costs associated with the project, including materials, labor, and overhead, before work begins. If the actual costs exceed the initial estimate, the contractor must absorb those additional expenses without any increase in the contract price. This risk is particularly significant in projects where unexpected conditions or changes in scope can occur. In contrast, other contract types distribute risk differently. A unit price contract allows for payment based on the actual quantity of work completed, minimizing risk for the contractor as they can adjust their pricing based on the work performed. Cost plus contracts provide reimbursement for the contractor's actual costs plus a fee, transferring much of the risk away from the contractor since they are not held to a fixed price. Lastly, a cost plus with a Guaranteed Maximum Price (GMP) offers a cap on costs, providing more security to the contractor while limiting their risk compared to a lump sum arrangement.

4. Which factor is most important in determining the critical path in project scheduling?

A. Early start times

B. Late start times

C. Activity durations

D. Resource availability

The most important factor in determining the critical path in project scheduling is activity durations. The critical path is the sequence of activities that dictates the minimum duration of the project. It is made up of activities that have zero float, meaning any delay in these activities directly impacts the overall project completion time. By analyzing the durations of each activity, project managers can identify which activities must be completed on time to prevent delays in the project. These durations help establish the total project timeline and reveal which activities are critical, hence determining the critical path. Other factors like early start times and late start times provide useful information regarding the scheduling flexibility of activities but do not directly affect the calculation of the critical path. Similarly, while resource availability is essential for project execution, it does not determine the critical path itself. Instead, it influences whether activities can be completed on time. Therefore, understanding the activity durations is key to effective project scheduling and management as it directly influences the critical path outcome.

SAMPLE

5. What is the primary role of the construction superintendent?

A. To handle all financial transactions

B. To oversee day-to-day construction operations on the job site

C. To design the architectural plans and layouts

D. To recruit and train subcontractors

The primary role of the construction superintendent is to oversee day-to-day construction operations on the job site. This includes managing workers, scheduling tasks, ensuring safety standards are maintained, and coordinating with different trades to ensure the project moves along efficiently and effectively. The superintendent acts as the on-site leader, responsible for making sure that the construction adheres to the project timeline and quality standards while also addressing any issues that arise during the construction process. The other roles mentioned, such as handling financial transactions, designing architectural plans, or recruiting and training subcontractors, do not fall under the superintendent's primary responsibilities. While construction superintendents may interact with these areas or collaborate with those who do, their main focus is the direct management of construction activities and personnel on site. This focus on operational oversight makes them essential for successful project execution.

6. For what type of project would you most likely use a trenching machine?

A. Residential basement excavation

B. Installing utility lines

C. Road construction

D. Site grading

A trenching machine is specifically designed to create narrow trenches in the ground, which makes it particularly suitable for projects involving the installation of utility lines. These machines can efficiently dig deep and narrow trenches with precision, allowing for the placement of water, sewer, gas, and electrical lines with minimal disruption to the surrounding area. In contrast, while trenching machines can be used for other types of excavation, they are not the most efficient tool for residential basement excavation, where broader and shallower digging is often required. For road construction, more extensive excavation for the foundation or roadway itself is usually needed, again making trenching machines less suitable. Similarly, site grading involves leveling and reshaping large areas of land, which is better accomplished with different types of earth-moving equipment rather than a trenching machine. Thus, the most fitting application of a trenching machine aligns with the installation of utility lines.

SAMPLE

7. When should meeting minutes be distributed?

A. about one day prior to the meeting

B. at the beginning of the meeting

C. about one day after the meeting

D. any time during the project

Distributing meeting minutes about one day after the meeting serves several important purposes. First, it allows the person responsible for documenting the minutes to accurately compile the discussions, decisions made, and action items identified during the meeting. This time gives them the chance to clarify points that may have been discussed, ensure that all relevant information is captured, and correct any misunderstandings or inaccuracies that might exist in the immediate aftermath of a meeting. Additionally, sending out the minutes approximately one day after the meeting helps ensure that participants have enough time to reflect on the discussions while the information is still fresh in their minds. This leads to a better understanding of the assigned tasks and encourages accountability, as team members can see what they are responsible for moving forward. Timing for the distribution of meeting minutes is also crucial for the overall flow of communication and workflow within a project. If minutes are sent out too soon, they may be incomplete or inaccurate, whereas sending them out significantly later could lead to participants forgetting key points or action items. This practice reflects a standard approach in project management to maintain clear and effective communication among team members, ultimately supporting project objectives and collaboration.

8. In construction, what do the term "submittals" refer to?

A. Final project delivery documents

B. Documents for acquiring insurance

C. Documents provided for approval before starting work

D. Payments made to contractors

The term "submittals" in construction refers specifically to documents that are submitted to the architect, engineer, or owner for approval before any construction work begins. These documents typically include shop drawings, product data, samples, and other materials that ensure compliance with the project specifications and requirements. The purpose of submittals is to verify that the contractor understands the project requirements and is prepared to meet them before commencing with the actual work on-site. This process is crucial because it allows for early identification of any potential issues or discrepancies that might arise, ensuring that all parties are aligned on the expectations for quality, performance, and aesthetic outcomes. By obtaining approval of these documents ahead of time, it reduces the risk of delays and modifications once the work is underway. The other options do not accurately define the term "submittals." Final project delivery documents typically refer to the concluding paperwork at the end of a project, while documents for acquiring insurance relate to risk management rather than project execution. Payments made to contractors represent financial transactions rather than preparatory documentation required for project execution.

SAMPLE

9. Which management system was developed based on Toyota's Production System?

A. TQM

B. Six Sigma

C. Lean

D. ISO 9000

Lean management is the correct choice, as it is derived from the principles of the Toyota Production System (TPS). TPS focuses on maximizing efficiency, minimizing waste, and improving the flow of work processes. Lean management adopts these principles and applies them to various industries to streamline operations, enhance productivity, and deliver more value to customers. The foundation of Lean lies in the idea of continuous improvement, which is characteristic of TPS. Lean practices emphasize eliminating non-value-adding activities, optimizing processes, and promoting a culture of efficiency and quality. By effectively managing resources and time, organizations can achieve higher performance levels and better meet customer demands. In contrast, while Total Quality Management (TQM), Six Sigma, and ISO 9000 all aim to improve quality and efficiency within organizations, they do not specifically arise from the Toyota Production System in the same way Lean does. TQM focuses on organizational-wide quality improvement processes, Six Sigma is aimed at process improvement through statistical methods, and ISO 9000 refers to a set of international standards for quality management systems.

10. What document defines the project's objectives and overall purpose?

A. Project Plan

B. Project Charter

C. Statement of Work

D. Risk Management Plan

The project charter is a vital document that outlines the project's objectives, overall purpose, and high-level requirements necessary for achieving those objectives. It serves as the foundation for the project, establishing the initial scope, stakeholders, and constraints. This document is typically created early in the project lifecycle and is essential for gaining approval from sponsors and stakeholders. By clearly defining the project's goals and aligning stakeholders' expectations, the project charter facilitates communication and sets the direction for all subsequent planning and execution. It ensures that everyone involved has a shared understanding of the project's intended outcomes. In contrast, other documents such as the project plan provide detailed schedules, resources, and execution strategies, while the statement of work focuses on the specific deliverables and work required. A risk management plan identifies potential risks and strategies to mitigate them but does not encapsulate the overall purpose and objectives of the project. Thus, the project charter is the central document that articulates the "why" behind the project, making it the key element required for project initiation.

SAMPLE

Next Steps

Congratulations on reaching the final section of this guide. You've taken a meaningful step toward passing your certification exam and advancing your career.

As you continue preparing, remember that consistent practice, review, and self-reflection are key to success. Make time to revisit difficult topics, simulate exam conditions, and track your progress along the way.

If you need help, have suggestions, or want to share feedback, we'd love to hear from you. Reach out to our team at hello@examzify.com.

Or visit your dedicated course page for more study tools and resources:

https://caclevel1.examzify.com

We wish you the very best on your exam journey. You've got this!

SAMPLE