MICHIGAN BUILDERS LICENSE PRACTICE EXAM (SAMPLE)

STUDY GUIDE



SAMPLE STUDY GUIDE WITH LIMITED QUESTIONS

VISIT US ONLINE FOR THE FULL VERSION STUDY GUIDE

https://michiganbuilderslicense.examzify.com

Copyright © 2026 by Examzify - A Kaluba Technologies Inc. product.

ALL RIGHTS RESERVED.

No part of this book may be reproduced or transferred in any form or by any means, graphic, electronic, or mechanical, including photocopying, recording, web distribution, taping, or by any information storage retrieval system, without the written permission of the author.

Notice: Examzify makes every reasonable effort to obtain accurate, complete, and timely information about this product from reliable sources.

SAMPLE

Table of Contents

Copyright 1

Table of Contents 2

Introduction 3

How to Use This Guide 4

Questions 5

Answers 8

Explanations 10

Next Steps 16

SAMPLE

Introduction

Preparing for a certification exam can feel overwhelming, but with the right tools, it becomes an opportunity to build confidence, sharpen your skills, and move one step closer to your goals. At Examzify, we believe that effective exam preparation isn't just about memorization, it's about understanding the material, identifying knowledge gaps, and building the test-taking strategies that lead to success.

This guide was designed to help you do exactly that.

Whether you're preparing for a licensing exam, professional certification, or entry-level qualification, this book offers structured practice to reinforce key concepts. You'll find a wide range of multiple-choice questions, each followed by clear explanations to help you understand not just the right answer, but why it's correct.

The content in this guide is based on real-world exam objectives and aligned with the types of questions and topics commonly found on official tests. It's ideal for learners who want to:

- Practice answering questions under realistic conditions,
- Improve accuracy and speed,
- Review explanations to strengthen weak areas, and
- Approach the exam with greater confidence.

We recommend using this book not as a stand-alone study tool, but alongside other resources like flashcards, textbooks, or hands-on training. For best results, we recommend working through each question, reflecting on the explanation provided, and revisiting the topics that challenge you most.

Remember: successful test preparation isn't about getting every question right the first time, it's about learning from your mistakes and improving over time. Stay focused, trust the process, and know that every page you turn brings you closer to success.

Let's begin.

SAMPLE

How to Use This Guide

This guide is designed to help you study more effectively and approach your exam with confidence. Whether you're reviewing for the first time or doing a final refresh, here's how to get the most out of your Examzify study guide:

1. Start with a Diagnostic Review

Skim through the questions to get a sense of what you know and what you need to focus on. Your goal is to identify knowledge gaps early.

2. Study in Short, Focused Sessions

Break your study time into manageable blocks (e.g. 30 – 45 minutes). Review a handful of questions, reflect on the explanations.

3. Learn from the Explanations

After answering a question, always read the explanation, even if you got it right. It reinforces key points, corrects misunderstandings, and teaches subtle distinctions between similar answers.

4. Track Your Progress

Use bookmarks or notes (if reading digitally) to mark difficult questions. Revisit these regularly and track improvements over time.

5. Simulate the Real Exam

Once you're comfortable, try taking a full set of questions without pausing. Set a timer and simulate test-day conditions to build confidence and time management skills.

6. Repeat and Review

Don't just study once, repetition builds retention. Re-attempt questions after a few days and revisit explanations to reinforce learning. Pair this guide with other Examzify tools like flashcards, and digital practice tests to strengthen your preparation across formats.

There's no single right way to study, but consistent, thoughtful effort always wins. Use this guide flexibly, adapt the tips above to fit your pace and learning style. You've got this!

SAMPLE

Questions

SAMPLE

1. What type of breach occurs when a contractor fails to clean the job site adequately?

A. Material breach

B. Immaterial breach

C. Fundamental breach

D. Minor breach

2. An occupational injury and illness log must be kept at every job site for businesses with more than how many employees?

A. 5

B. 10

C. 15

D. 20

3. In a solid concrete foundation wall, anchor bolts for the sill plate should be spaced no more than how far apart?

A. 4 feet apart

B. 6 feet apart

C. 8 feet apart

D. 10 feet apart

4. A comprehensive Hazard Communication program includes which of the following?

A. Worker training

B. Container labeling

C. SDS availability

D. Emergency procedures

5. What is another term for a combined construction loan and mortgage?

A. Bridge loan

B. Permanent financing

C. Construction permanent loan

D. Short-term loan

SAMPLE

6. What should contractors be aware of if they have a FUTA liability greater than a specified amount?

A. They must pay additional fees

B. They must deposit taxes quarterly

C. They receive tax credits

D. They file reports annually

7. Which of these is NOT another term for fake stone products?

A. Artificial stone

B. Imitation stone

C. Natural stone

D. Manufactured stone

8. What is the minimum number of coats of Portland plaster required on the exterior over masonry?

A. 1 coat

B. 2 coats

C. 3 coats

D. 4 coats

9. Which type of management involves understanding the financial and human resources required for a project?

A. Cost management

B. Time management

C. Quality management

D. Resource management

10. Fire blocking can be required in walls over what height?

A. 5 feet

B. 10 feet

C. 12 feet

D. 15 feet

SAMPLE

Answers

SAMPLE

1. B
2. B
3. B
4. B
5. C
6. B
7. C
8. B
9. A
10. B

SAMPLE

Explanations

SAMPLE

1. What type of breach occurs when a contractor fails to clean the job site adequately?

A. Material breach

B. Immaterial breach

C. Fundamental breach

D. Minor breach

In the context of a contractor's obligations, an immaterial breach refers to a violation of a contractual requirement that does not significantly affect the overall purpose or functionality of the contract. When a contractor fails to clean the job site adequately, it is typically seen as an oversight that, while it may create inconvenience or minor issues, does not undermine the primary objectives of the construction project. The significance of this concept lies in the idea that certain breaches might not warrant serious repercussions or the right for the other party to terminate the contract or seek damages. The primary performance of the contract—delivering the project as agreed—has still been achieved, which is why this breach is considered immaterial rather than a more serious type of breach that would have greater implications. In contrast, types of breaches like material or fundamental would imply a more serious failure that impacts the core agreement and may lead to legal action or contract termination. A minor breach, on the other hand, may align closely with an immaterial breach but can sometimes refer to violations that involve compensation or rectification without greatly affecting the contractual relationship. Therefore, identifying the breach correctly is essential for understanding the potential remedies and obligations for both parties involved in a construction contract in Michigan.

2. An occupational injury and illness log must be kept at every job site for businesses with more than how many employees?

A. 5

B. 10

C. 15

D. 20

The requirement to keep an occupational injury and illness log is tied to the regulations set forth by the Occupational Safety and Health Administration (OSHA). For businesses that have 10 or more employees, it is mandated to maintain these logs at their job sites. This is crucial not only for tracking workplace injuries and illnesses but also for ensuring that employers comply with safety regulations and can respond appropriately to any safety issues that may arise. Businesses with fewer than 10 employees are typically exempt from this requirement, as they may have less frequent occurrences of injury and illness data to track. However, once the employee count reaches 10, the obligation to document and maintain this log comes into effect, allowing for better oversight and enhancement of workplace safety protocols. Thus, the correct answer reflects the legal threshold for maintaining these important records and underscores the significance of occupational safety management in relation to workforce size.

SAMPLE

3. In a solid concrete foundation wall, anchor bolts for the sill plate should be spaced no more than how far apart?

A. 4 feet apart

B. 6 feet apart

C. 8 feet apart

D. 10 feet apart

The correct spacing for anchor bolts in a solid concrete foundation wall is no more than 6 feet apart. This spacing is critical for ensuring that the sill plate is securely fastened to the foundation, providing the necessary structural support and stability for the building above. When anchor bolts are spaced appropriately, they help to distribute the load from the structure evenly across the foundation, reducing the risk of movement or shifting that can lead to structural issues. Spacing them too far apart could compromise the integrity of the connection between the sill plate and the foundation, potentially leading to failure in the structural framing over time. In addition to providing adequate support, proper spacing also complies with building codes and industry standards, which are designed to ensure safety and durability in construction. Thus, adhering to the guideline of a maximum spacing of 6 feet for anchor bolts is essential for achieving a robust foundation system.

4. A comprehensive Hazard Communication program includes which of the following?

A. Worker training

B. Container labeling

C. SDS availability

D. Emergency procedures

A comprehensive Hazard Communication program is designed to ensure that all employees are aware of the hazardous materials they may encounter in the workplace and how to handle them safely. Container labeling is a vital component of this program, as it provides immediate information about the contents of a container, including the identity of the chemical, hazard warnings, and the manufacturer's information. This labeling helps workers quickly understand the dangers associated with a particular substance and the precautions they need to take when handling it. While worker training, SDS availability, and emergency procedures are also important aspects of a Hazard Communication program, they serve to support the central purpose of effective communication about hazards. Training helps workers understand labels and SDS, while emergency procedures ensure safety in case of an incident. However, labeling is critical because it directly communicates hazard information at the point of use. Therefore, container labeling stands out as an essential element in a comprehensive program focused on hazard communication.

SAMPLE

5. What is another term for a combined construction loan and mortgage?

A. Bridge loan

B. Permanent financing

C. Construction permanent loan

D. Short-term loan

A combined construction loan and mortgage is often referred to as a construction permanent loan. This type of financing is specifically designed for projects that involve both the construction phase and the long-term mortgage phase, allowing the borrower to secure funding for the construction of a home and then transition into a permanent mortgage without taking out separate loans for each phase. This type of loan streamlines the borrowing process, as the borrower only needs to go through the application and closing processes once, simplifying both the management of payments and the organization of financing. Once construction is complete, the loan converts to a permanent mortgage, making it an efficient option for borrowers looking to build new homes.

6. What should contractors be aware of if they have a FUTA liability greater than a specified amount?

A. They must pay additional fees

B. They must deposit taxes quarterly

C. They receive tax credits

D. They file reports annually

When contractors have a Federal Unemployment Tax Act (FUTA) liability that exceeds a specified amount, they are required to deposit FUTA taxes quarterly. This obligation arises because the federal government has established certain thresholds, and once a contractor's liability surpasses this limit, the frequency of tax payments increases to ensure that obligations are met in a timely manner. Quarterly deposits help streamline the tax process and ensure that funds are available for unemployment compensation programs. This is particularly important for businesses as it aids in maintaining compliance with federal regulations and helps avoid potential penalties for non-compliance due to underpayment or late payment of taxes. Additionally, while factors such as tax credits or reporting requirements are important aspects of tax compliance, they are separate from the immediate responsibilities associated with larger FUTA liabilities, which focus directly on the timing and frequency of payments.

SAMPLE

7. Which of these is NOT another term for fake stone products?

A. Artificial stone

B. Imitation stone

C. Natural stone

D. Manufactured stone

The correct answer highlights that "natural stone" is distinct from the other terms listed, which all refer to synthetic or non-natural products. Natural stone is a term used to describe materials that are directly obtained from the earth, such as granite, marble, or limestone. These stones are quarried and presented in their authentic form, retaining the properties and characteristics that the earth has imparted to them over time. In contrast, the other terms—artificial stone, imitation stone, and manufactured stone—specifically denote products created through human intervention. Artificial stone often refers to materials made from polymers, aggregates, and resins, designed to replicate the aesthetic qualities of genuine stone. Imitation stone suggests that the material is made to visually mimic the look of real stone, without being made from actual stone. Manufactured stone, similarly, encompasses a wide range of products crafted through industrial processes to simulate the appearance and texture of natural stone while often being lighter and more cost-effective. By understanding these distinctions, it becomes clear that natural stone is not only different in composition and origin but also recognized for its authenticity, setting it apart from the other synthetic alternatives.

8. What is the minimum number of coats of Portland plaster required on the exterior over masonry?

A. 1 coat

B. 2 coats

C. 3 coats

D. 4 coats

The minimum number of coats of Portland plaster required on the exterior over masonry is indeed two coats. This requirement is based on standard practices within the construction industry, which aim to ensure durability, moisture resistance, and aesthetic appeal for plaster finishes. The first coat, known as the scratch coat, is applied to create a key for the second coat, allowing better adhesion. This scratch coat also helps to level the surface to some extent. Once it has cured, the second coat, often referred to as the brown coat, is applied. This coat provides the necessary thickness and smoothness to the plaster finish. By using two coats, builders can ensure that the plaster has sufficient bonding to the underlying masonry and can withstand weathering, reducing the risks of cracking or delamination that might occur with fewer coats. This method is a recognized standard, particularly in climates with varying conditions that can affect building materials. The other options suggest a lower number of coats than recommended, which would compromise the integrity and effectiveness of the plaster system.

SAMPLE

9. Which type of management involves understanding the financial and human resources required for a project?

A. Cost management

B. Time management

C. Quality management

D. Resource management

The concept of management that focuses on understanding the financial and human resources needed for a project is best captured by cost management. Cost management encompasses the processes involved in planning and controlling the budget of a project. This includes estimating costs, determining a budget, and managing project expenditures to ensure that the project is completed within the approved budget. Effective cost management is vital to a project's success, as it helps to identify financial resources required to complete various project tasks and to allocate them appropriately. While other forms of management, like time management and quality management, are essential for ensuring a project stays on schedule and meets quality standards, respectively, they do not directly involve the assessment and management of financial and human resources. Resource management, on the other hand, is a broader category that overlaps with the aspects of managing both human resources and materials but does not specifically emphasize financial resources. Therefore, cost management is the most suitable answer to the question regarding understanding the financial and human resources required for a project.

10. Fire blocking can be required in walls over what height?

A. 5 feet

B. 10 feet

C. 12 feet

D. 15 feet

Fire blocking is a crucial fire safety measure designed to prevent the spread of flames and smoke through wall cavities. In many building codes, the requirement for fire blocking typically applies to walls that exceed a certain height, which often aligns with 10 feet. When walls are built over this height, there is a greater risk for fire to travel within concealed spaces, and fire blocking serves to compartmentalize these areas, slowing down the progression of a fire. This means that for structures with walls taller than 10 feet, fire blocking is mandated to enhance safety and compliance with the building standards. The other height options do not generally reflect the common code requirements that have been established to address fire hazards in taller structures. Therefore, the 10-foot mark represents a practical threshold for ensuring fire safety within building design and construction.

SAMPLE

Next Steps

Congratulations on reaching the final section of this guide. You've taken a meaningful step toward passing your certification exam and advancing your career.

As you continue preparing, remember that consistent practice, review, and self-reflection are key to success. Make time to revisit difficult topics, simulate exam conditions, and track your progress along the way.

If you need help, have suggestions, or want to share feedback, we'd love to hear from you. Reach out to our team at hello@examzify.com.

Or visit your dedicated course page for more study tools and resources:

https://michiganbuilderslicense.examzify.com

We wish you the very best on your exam journey. You've got this!

SAMPLE